BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2021-22/OW/WORK_INDENT50349

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/15/2021-22, Date: 18-02-2022

Name of Work:Improvements to drains Kuvempu layout kempapura in ward no.07 byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SIDDESHA ( )	
				In Figures	In Words
1	222.75	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications	cum	118.0	Rupees One Hundred Eighteen Only
2	29.88	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification	cum	5078.0	Rupees Five Thousand Seventy Eight Only
3	47.03	Providing and laying in plain reinforced cement concrete mix 1:2:4 with OPC @ 240 kgs, with 40 mm and down size graded granite matel coarse aggregates @ 0.84 cum and fine aggragtes @ 0.56cum, in pen foundations including including cost of all materials, labour HOM machinery form works scaffolding and centering complete as per sprcifications complete as per drawing anf techinal specifications	cum	5105.0	Rupees Five Thousand One Hundred Five Only
4	2.35	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	tonne	77912.0	Rupees Seventy Seven Thousand Nine Hundred Twelve Only
5	796.8	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge	sqm	415.0	Rupees Four Hundred Fifteen Only
6	99.6	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications	sqm	2009.0	Rupees Two Thousand Nine Only
7	222.75	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	cum	81.0	Rupees Eighty One Only

Siddesh

Signature of the Contractor

Executive Engineer
Byarayanapura Division 21/04
BBMP, Bangalore - 92

21/04